




Features	Test Method	Value
Length and Width	ISO 10545 - 2	$\pm 0.5\%$, $\pm 2\text{mm}$
Thickness		$\pm 5\%$, $\pm 0.5\text{mm}$
Straightness of Sides		$\pm 0.5\%$, $\pm 1.5\text{mm}$
Rectangularity		$\pm 0.3\%$, $\pm 2\text{mm}$
Surface Flatness		$\pm 0.5\%$, $\pm 2\text{mm}$
Surface Quality		Min. 95% of tiles free of visible defects
Water Absorption	ISO 10545 - 3	$E \leq 0.1\%$ Bla GL
Modulus of Rupture / Breaking Strength	ISO 10545 - 4	$R \geq 35 \text{ N/mm}^2$
Bending Strength		$S \geq 1300 \text{ N}$
Coefficient of Linear Thermal Expansion	ISO 10545 - 8	Resistant
Thermal Shock Resistance	ISO 10545 - 9	Resistant
Crazing Resistance	ISO 10545 - 11	Resistant
Chemical Resistance (Domesitic)	ISO 10545 - 13	A
Chemical Resistance (Low Concentration)		LA
Chemical Resistance (High Concentration)		HA
Fire Resistance	-	A1/A1 _{FL}
Slip Resistance	-	DCOF Does Not Pass
LEED		Yes
Recycled Content		5.22%
VOC Emissions		Zero VOC
Environmental Product Declaration	-	Facility-Specific

This product will contricute to USGBC registered LEED projects.
 It will also contricute to the ANSI approved NAHB Green Building Standard ICC 700.

According to ANSI and MIA standards, depending on the type and size of tile, it is recommended to have at least a 1/8" wide grout joint for floor tiles in order to be able to fill the grout joint full and never less than 1/16" wide. Please refer to TCNA guidelines for more on grout recommendations.

Disclaimer: DCOF wet and dry is different on every production lot and can vary. This number represents the average DCOF of the tested production lots. If the spec listed is over the minimum standard, it will meet the requirement.

Product Info:

- Glazed Porcelain Tile
- Semi Polished Finish
- 10mm Thickness
- Pressed Edge
- PEI Rating = 3 - 4
- V3 - Moderate Variation
- Frost Resistance = Yes



www.genrose.com

Contact your sales representative for more information. All material must be inspected prior to installation. Absolutely no claims will be accepted after installation.