

| Features | Test Method | Value | |
|--|----------------|--|--------------|
| Dimensions | ISO 10545 - 2 | Compliant | |
| Surface Quality | | Min. 95% of tiles free of visible defects | |
| Water Absorption | ISO 10545 - 3 | < 0.2% | |
| Modulus of Rupture / Bending Strength | ISO 10545 - 4 | > 40 N/mm ² | |
| Breaking Strength | | ≥ 1300 N | |
| Coefficient of Linear Thermal Expansion | ISO 10545 - 8 | $\alpha \leq 7.1 \times 10^{-6} \text{ }^{\circ}\text{C}^{-1}$ | |
| Thermal Shock Resistance | ISO 10545 - 9 | Resistant | |
| Crazing Resistance | ISO 10545 - 11 | Resistant | |
| Chemical Resistance (Domestic) | ISO 10545 - 13 | A | |
| Chemical Resistance (Low Concentration) | | LA | |
| Chemical Resistance (High Concentration) | | HA | |
| Fire Resistance | - | A1/A1 _{FL} | |
| Slip Resistance | ANSI A326.3 | Polished | Matte |
| | | DCOF Does Not Pass | DCOF 0.43 |
| LEED | - | Yes | |
| Recycled Content | - | ≥ 50% | |
| VOC Emissions | - | Zero VOC | |
| Declare | - | Red List Free | |
| Environmental Product Declaration | - | Facility-Specific | |



This product will contribute to USGBC registered LEED projects. It will also contribute to the ANSI approved NAHB Green Building Standard ICC 700.

According to ANSI and MIA standards, depending on the type and size of tile, it is recommended to have at least a 1/8" wide grout joint for floor tiles in order to be able to fill the grout joint full and never less than 1/16" wide. Please refer to TCNA guidelines for more on grout recommendations.

Disclaimer: DCOF wet and dry is different on every production lot and can vary. This number represents the average DCOF of the tested production lots. If the spec listed is over the minimum standard, it will meet the requirement.

Product Info:

- Glazed Porcelain Tile
- Matte | Polished Finishes
- V1 - Uniform Appearance (White | Black)
- V2 - Slight Shading Variation (Light Grey | Blu | Emerald)
- 9.5mm Thickness
- Pressed Edge
- Frost Resistance = Yes



www.genrose.com

Contact your sales representative for more information. All material must be inspected prior to installation. Absolutely no claims will be accepted after installation.