

Features	Test Method	Value		
Length and Width	ISO 10545 - 2	± 0.6		
Thickness		± 5.0%		
Straightness of Sides		± 0.5%		
Rectangularity		± 0.5%		
Surface Flatness		± 0.5%		
Surface Quality		Min. 95% of tiles free of visible defects		
Water Absorption		ISO 10545 - 3	≤ 0.5%	
Modulus of Rupture / Bending Strength	ISO 10545 - 4	R ≥ 40 N/mm ²		
Breaking Strength		Tiles	Slab	
		S ≥ 1800 N	S ≥ 1100 N	
Deep Abrasion Resistance	ISO 10545 - 6	8.5mm	9mm	
		-	≤ 150 mm ³	
Coefficient of Linear Thermal Expansion	ISO 10545 - 8	≤ 7 (MK) - 1		
Thermal Shock Resistance	ISO 10545 - 9	Resistant		
Crazing Resistance	ISO 10545 - 11	Resistant		
Chemical Resistance (Domestic)	ISO 10545 - 13	A		
Chemical Resistance (Low Concentration)		LA		
Chemical Resistance (High Concentration)		HA		
Fire Resistance	-	A1/A1fl		
Slip Resistance (Wet)	ANSI A326.3	3" x 24"	Matte	Anti - Slip
		DCOF 0.50	DCOF 0.67	DCOF 0.74
Recycled Content	-	> 20%		
LEED	-	Yes		
Environmental Product Declaration	-	Facility Specific		
Health Product Declaration	-	Certificate Available		
Declare	-	Red List Free		
VOC Emissions	-	Zero VOC		



Declare.

This product will contribute to USGBC registered LEED projects. It will also contribute to the ANSI approved NAHB Green Building Standard ICC 700.

According to ANSI and MIA standards, depending on the type and size of tile, it is recommended to have at least a 1/8" wide grout joint for floor tiles in order to be able to fill the grout joint full and never less than 1/16" wide. Please refer to TCNA guidelines for more on grout recommendations.

Disclaimer: DCOF wet and dry is different on every production lot and can vary. This number represents the average DCOF of the tested production lots. If the spec listed is over the minimum standard, it will meet the requirement.

Product Info:

- Glazed Porcelain Tile
- Matte | Matte/Glossy Finishes
- 8.5mm | 9mm Thickness
- Pressed | Rectified Edges
- V3 - Moderate Variation
- Frost Resistant



www.genrose.com

Contact your sales representative for more information. All material must be inspected prior to installation. Absolutely no claims will be accepted after installation.